



Due to the variety of configurations, please consult the factory to discuss application requirements and for complete specifications and price quotations.

Approvals



Package includes: Weighbridge steel; weighbridge fasteners; load cells with conduit fitting; load cell mounts with leveling bolts and anchor bolts; copper transient bypass cables at each load cell; FRP junction box(es); summing board; homerun cable to indicator (60 ft long); print packages including deck assembly, foundation drawing (pier and floating slab) and rebar placement for deck concrete; installation manual with truck loading/unloading diagram. Please refer to catalog page for equipment which is included with each model.

Package does not include: Cable runs; corrugated sheeting for concrete deck; rebar for concrete deck; approach coping; foundation alignment posts; rebar and mesh for foundation; concrete; indicator; printer; freight charges including material handling, shipping charges, transportation permits and fees, escort(s) charge, and insurance transportation fees.

Standard Features

- 75,000 lb load cells and G-force mounts
- Up to 270,000 lb full scale capacity
- NTEP Certified
- Available in various configurations
- Standard widths from 10 to 14 ft